

表1-1 工程量清单表

项目名称: 巴林右旗查干诺尔镇上石村易地搬迁后续扶持过水路面修复项目

标段：巴林右旗查干诺尔镇上石村易地搬迁后续扶持过水路面修复项目

第 1 页

共 4 页

[illegible]

清单 第200章 路基养护工程

Y201	场地清理				
Y201-2	拆除结构物				
Y201-2-3	砌体结构	m3	556.70		
Y202	路基挖方				
Y202-1	路基挖方				
Y202-1-1	挖土方	m3	4896.00		
Y202-2	路基填筑				
Y202-2-8	结构物台背回填	m3	2474.40		
Y204	路基防护养护				
Y204-1	防护工程修复与加固				
Y204-1-1	护坡、护面墙修复与加固				
Y204-1-1-4	现浇混凝土				
-a	C25片石砼基础	m3	123.00		
-b	C25片石混凝土铺砌	m3	1200.40		
-c	C30片石砼坡面	m3	188.30		
-d	C25砼消力坎	m3	37.40		
Y204-5	防护设施增设				
Y204-5-1	喷射混凝土和喷浆边坡				
Y204-5-1-2	土工合成材料	m2	559.00		
Y204-5-2	沿河路基防护				
Y204-5-2-6	石笼防护	m3	446.80		
Y204-5-4	挡土墙				
Y204-5-4-1	垫层				
-a	砂砾垫层	m3	329.00		
Y204-5-4-5	片石混凝土挡土墙				
-a	C25片石混凝土隔水墙	m3	888.60		
Y204-5-4-7	浇筑悬空C25混凝土				
	浇筑悬空C25混凝土	m3	129.60		
清单 第200章 合计 人民币 (元)					

